

PORTA-KING

Fully-Assembled Modular Building Systems

A Totally Integrated, Fully-Assembled System That Can Be Easily Moved Anywhere ... Anytime.

The Porta-King Fully-Assembled Modular System provides you with complete building versatility and substantial savings in construction costs. Simply forklift the system into place and connect to a power supply. You eliminate the costs for on-site labor and the coordination of various other trades - plus, accelerated capital equipment depreciation may apply. If you need to move or relocate the building, simply disconnect the utilities and forklift to a new location. It's just that simple.

Standard systems include switches, outlets and lights located where you want and come fully wired to a load center making main power connection fast and easy. All wiring is hidden within wiring chases located between panels. Snap-on raceway covers enable quick and easy access for repair, modification and additions to the electrical service.

The foundation of each system is a structural steel base with forklift

pockets. The available 1-3/4" or 3" thick wall panels provide excellent insulation and superior sound attenuation. In addition, all-anodized aluminum extrusions provide years of superior service: 1) Extruded anodized aluminum post/frame components won't rust like steel component systems when exposed to moisture in wash-down applications or in high humidity environments. 2) Heavy-duty extruded aluminum post connections provide a strong, tight fit between panels. This is because the extruding process enables tighter control over tolerances on critical dimensions when compared to the roll-forming process commonly used in steel support systems.

Standard floor construction consists of durable vinyl tile. Optional anti-fatigue matting, raised rubber disk, aluminum treadplate, carpet and other flooring materials available. Standard wall panels are vinyl covered hardboard available in eight standard colors, however, panels can be customized with a wide variety of panel finishes.

For the very best in fully-assembled modular building systems - at very competitive prices - Porta-King is the answer.

System Benefits:

- Very economically priced.
- Customize floor plans to meet your exact requirements.
- A full selection of doors, hardware and glazing available.
- Excellent for partial and full-height partition systems.
- Standard vinyl covered wall panels ensure easy cleaning and upkeep for reduced maintenance costs.
- Floor construction consists of two layers of solid 3/4" moisture resistant subfloor with durable vinyl tile covering.
- Maintenance-free anodized aluminum components provide superior durability compared to rust-prone steel component systems.
- Optional panel finishes include: vinyl covered drywall, fiberglass reinforced plastic, painted steel, embossed anodized aluminum, and acoustical carpet or fabric.
- Optional panel construction can accommodate UL Class 1 or non-combustible fire classification.

Perfect for:

In-Plant Offices
Restrooms
Supervisor Offices
Work Stations
Control Rooms
Computer Rooms
First Aid Stations
Quality Control Rooms
Much More

**DESIGN IT
ON THE WEB**
www.portaking.com

PORTA-KING

4133 Shoreline Drive
Earth City, MO 63045
Phone: 314-291-4200
Fax: 314-291-2857
TOLL FREE: 800-284-5346
www.portaking.com

Put A Fully Functional Restroom In Your Facility ... Fast!

Porta-King fully-assembled restrooms help you to quickly and economically:

- 1) Accommodate additional personnel
- 2) Provide gender-based facilities
- 3) Meet imposed compliance with ADA regulations

Systems come pre-wired and pre-plumbed from the factory with specified lights, outlets, lavatories, sinks, urinals, etc. - just hook up the electrical, water and gray lines. Chase walls with access doors enable quick, on-site plumbing connections. Or, you can elect to have the units plumbed on site.

